

# On-Site M&I Return Flow

as percentage of total volume of water entering the supply system

DATA Sources	Technical Report	LACWWD40 Mr. Ariki Testimony	Palmdale Sewer Plan/ Census 2010	LACWWD40 Water Master Plan 2010	California DWR 2011
Critical DATA	Historic 1946 - 2005	In/Out 30/70 %	Septic Effluent 61 gal/pers day	Supply Leaks 3%	Evapo-Transpiration
Sewage Leakage	NA	NA	0.0	0.0	0.0
Supply System Leakage	NA	NA	NA	1.8	0.7
Irrigation Leakage	NA	NA	NA	1.6	0.3
Over-irrigation	11.0	14.0	14.0	10.6	1.0
Septic Tank Effluents	17.1	11.4	5.6	5.6	3.7
<b>TOTAL</b>	<b>28.1</b>	<b>25.4</b>	<b>19.6</b>	<b>19.6</b>	<b>5.7</b>